



higher education
& training
Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



BUFFALO CITY
TVET COLLEGE

REQUEST FOR QUOTATION: FLOOR COVERING

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to weziwe@bccollege.co.za; cc: zimkhitha@bccollege.co.za

Kindly submit the following **COMPULSORY** documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Declaration forms (SBD 4, 8 and 9)
- Certified BEE certificate (0 points will be awarded for BEE certificates that are not certified)
- Tax Clearance Certificate
- CSD report
- Bank Confirmation Letter (not older than 3 months)

Closing Date: 08 December 2021 at 11h00am. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED

Enquiries: Ms Weziwe Gwabavu / Zimkhitha Jikwana

043 704 9241



Date: 29-11-2021

Enquiry: infrastructureac3@bccollege.co.za

SPECIFICATION OF FLOOR COVERING FOR KING STREET CAMPUS

No	Item	Description	Unit	Quantity
1	Ground floor Corridor	<ul style="list-style-type: none">Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for at the Reception	M ²	27
		<ul style="list-style-type: none">Install new vinyl laminated flooring. (Glued onto floor)Install new 70 x 22mm pine skirting	M	22
		<ul style="list-style-type: none">Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for at A3 office	M ²	38
		<ul style="list-style-type: none">Install new vinyl laminated flooring (Glued onto the floor)Install new 70 x 22mm pine skirting	M	26.40
		<ul style="list-style-type: none">Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for at the Passage	M ²	40.70
		<ul style="list-style-type: none">Install new vinyl laminated flooring. (Glued onto the floor)Install new 70 x 22mm pine skirting	M	55.60
		<ul style="list-style-type: none">Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for at A1 ClassroomApply two coats of timber sealer and two coats of mahogany varnish.Install new 70 x 22mm pine skirting	M ²	38.85
		<ul style="list-style-type: none">Prepare the wooden floor by sanding it, fill all gaps, broken timber to be	M	26.40
		<ul style="list-style-type: none">Prepare the wooden floor by sanding it, fill all gaps, broken timber to be	M ²	48.40

		<ul style="list-style-type: none"> repaired and allowed for at A2 Classroom Apply two coats of timber sealer and two coats of mahogany varnish. Install new 70 x 22mm pine skirting 	M	29.60
		<ul style="list-style-type: none"> Remove the existing vinyl tiles and prepare the concrete floor at all the Toilets at Ground Floor. Replace with new vinyl tiles Install new 70 x 22mm pine skirting 	M ²	25.45
		<ul style="list-style-type: none"> Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for at A8 Classroom Apply two coats of timber sealer and two coats of mahogany varnish. Install new 70 x 22mm pine skirting 	M ²	26.75
		<ul style="list-style-type: none"> Remove the existing matt at the Stairs Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for Replace with new Origins Balau Dark Brown EcoTec Matt Porcelain Floor Tile – 710 x 280mm Install new 70 x 22mm pine skirting 	M	20
		<ul style="list-style-type: none"> Remove the existing matt at the Stairs Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for Replace with new Origins Balau Dark Brown EcoTec Matt Porcelain Floor Tile – 710 x 280mm Install new 70 x 22mm pine skirting 	M ²	21.50
		<ul style="list-style-type: none"> Remove the existing matt at the Stairs Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for Replace with new Origins Balau Dark Brown EcoTec Matt Porcelain Floor Tile – 710 x 280mm Install new 70 x 22mm pine skirting 	M	32.60
2.	First Floor Corridor	<ul style="list-style-type: none"> Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for at the passage Install new vinyl laminated flooring. (Glued onto the floor) Install new 70 x 22mm pine skirting 	M ²	35.15
		<ul style="list-style-type: none"> Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for at B2 Store room 	M	40
		<ul style="list-style-type: none"> Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for at B2 Store room 	M ²	7.10

<ul style="list-style-type: none"> • Install new Origins Balau dark Brown EcoTec Mat Porcelain Floor Tile – 710 x 280mm tiles • Install new 70 x 22mm pine skirting 	M	9.70
<ul style="list-style-type: none"> • Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for at B4 Office • Apply two coats of sealer and two coats of mahogany varnish. • Install new 70 x 22mm pine skirting 	M ²	27
<ul style="list-style-type: none"> • Remove the existing vinyl tiles at the Toilets B10 & B11 • Prepare the surface • Install new vinyl tiles • Install new 70 x 22mm pine skirting 	M ²	10.10
<ul style="list-style-type: none"> • Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for at B8 Office • Apply two coats of timber sealer and apply two coats of mahogany varnish. • Install new 70 x 22mm pine skirting 	M	11.40
<ul style="list-style-type: none"> • Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for at B5 Office • Apply two coats of sealer and apply two coats of mahogany varnish. • Install new 70 x 22mm pine skirting 	M ²	33.5
<ul style="list-style-type: none"> • Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for at B5 Office • Apply two coats of sealer and apply two coats of mahogany varnish. • Install new 70 x 22mm pine skirting 	M	27
<ul style="list-style-type: none"> • Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for at B5 Office • Apply two coats of sealer and apply two coats of mahogany varnish. • Install new 70 x 22mm pine skirting 	M ²	38
<ul style="list-style-type: none"> • Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for at B1 Office 	M	25
<ul style="list-style-type: none"> • Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for at B1 Office 	M ²	15
	M	16


	<ul style="list-style-type: none"> Apply two coats of sealer and apply two coats of mahogany varnish. Install new 70 x 22mm pine skirting 		
	<ul style="list-style-type: none"> Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for at B7 Office Apply two coats of sealer and apply two coats of mahogany varnish. Install new 70 x 22mm pine skirting 	M ²	19.63
	<ul style="list-style-type: none"> Remove the existing vinyl tiles at the Staff Kitchen Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for Apply two coats of sealer and apply two coats of mahogany varnish. Allowance for the removal of the existing cupboard and wardrobe. Allowance of installing back the cupboard and wardrobe removed Install new 70 x 22mm pine skirting 	M ²	10
	<ul style="list-style-type: none"> Remove the existing vinyl tile at the Bathroom Prepare the wooden floor by sanding it, fill all gaps, broken timber to be repaired and allowed for Replace with new Origins Balau Dark Brown Matt Porcelain Tile – 710 x 28mm tiles Install new 70 x 22mm pine skirting 	M ²	8.21
		M	12

The quotation are to be submitted at Procurement Department together with: Certified BEE Certificate, Valid Tax Clearance Certificate ,CSD documents , bank confirmation letter and fill in SBD4, SBD8, and SBD9.


N.B Site visit is to be conducted on.....


Requester: O. Jwente


29/11/2021
Date


Project manager: L. Mda

29-11-2021
Date


AD Infrastructure: N. Ngxekana

29-11-2021
Date


AD SCM: S. Siwisa

29/11/2021
Date