



higher education  
& training  
Department  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY**  
**TVET COLLEGE**

### **REQUEST FOR QUOTATION: FLOOR COVERING (JKB)**

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to [quotations@bccollege.co.za](mailto:quotations@bccollege.co.za).

**TENDERERS MUST NOTE THAT WHEREVER THIS DOCUMENT REFERS TO ANY PARTICULAR TRADE MARK, NAME, PATENT, DESIGN, TYPE, SPECIFIC ORIGIN OR PRODUCER, SUCH REFERENCE SHALL BE DEEMED TO BE ACCOMPANIED BY THE WORDS 'OR EQUIVALENT.**

Kindly submit the following **REQUIRED** documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Declaration forms (SBD 4, 8 and 9)
- Certified BEE certificate (0 points will be awarded for BEE certificates that are not certified)
- Valid Tax Clearance Certificate
- CSD report
- Bank Confirmation Letter (not older than 3 months)
- Quotations must be detailed as per specification
- **N. B. Compulsory site briefing session will be held at John Knox Bokwe on 9<sup>th</sup> November 2022 @ 11 Am.**

**Closing Date: 15 November 2022 at 12:00 Pm. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED**

Enquiries: Ms Weziwe Gwabavu / Zimkhitha Jikwana

043 704 9241

---



# higher education & training

Department:  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA



## BUFFALO CITY TVET COLLEGE

### REQUEST FOR QUOTATIONS

BUFFALO CITY TVET COLLEGE KINDLY REQUEST PRICED QUOTATIONS FROM POTENTIAL SERVICE PROVIDERS. THE SERVICES REQUIRED ARE FOR THE REPLACEMENT OF FLOOR COVERINGS UNTO VARIOUS AREAS LISTED BELOW ON THE SPECIFICATION

**CIDB GRADING 1GB or Higher**

ITEM	DESCRIPTION AND REQUIRMENTS	Unit	QTY	Rate	Price
<b>Venue: Portfollo Room</b>					
1	Uplifting of existing carpet tiles	M <sup>2</sup>	35.28		
2	Removal of all skirting and quadrants	M	23.19		
3	Removal of carpet tile adhesive from floors in order to obtain level and clean substrate which is conducive to laying of the new laminate flooring.	M <sup>2</sup>	35.28		
4	Prepare the existing floor to receive new floor covering	M <sup>2</sup>	35.28		
5	Installation of vinyl laminate flooring (10mm, industrial class 32 commercial grade with AC4 wear resistance) (Colour to be selected upon award)	M <sup>2</sup>	35.28		
6	Removal of existing skirting	M	23.19		
7	Installation of 70mm pine skirting. Skirting to be applied x2 coats of varnish (Colour to be discussed upon award)	M	23.19		
8	Removal of existing quadrant	M	23.19		
9	Installation of new 16mm pine quadrant. Quadrant to be varnished (Colour to be discussed upon award)	M	23.19		
10	Trimming of doors to meet floor level	Each	1		
11	Installation of aluminium reducer in door opening (40mm)	Each	0.82m		
<b>Venue : Resource Centre (Upper Level)</b>					
1	Uplifting of existing carpet tiles	M <sup>2</sup>	214		
2	Removal of all skirting and quadrants	M	107.72		
3	Removal of carpet tile adhesive from floors in order to obtain level and clean substrate which is conducive to laying of the new laminate flooring.	M <sup>2</sup>	214		
4	Prepare the existing floor to receive new floor covering	M <sup>2</sup>	214		
5	Installation of vinyl laminate flooring (10mm, industrial class 32 commercial grade with AC4 wear resistance) (Colour to be selected upon award)	M <sup>2</sup>	214		
6	Removal of existing skirting	M	107.72		
7	Installation of 70mm pine skirting. Skirting to be applied x2 coats of varnish (Colour to be discussed upon award)	M	107.72		



# higher education & training

Department:  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA



## BUFFALO CITY TVET COLLEGE

8	Removal of existing quadrant	M	107.72		
9	Installation of new 16mm pine quadrant. Quadrant to be varnished (Colour to be discussed upon award)	M	107.72		
10	Trimming of doors to meet floor level	Each	7		
11	Installation of aluminium reducer in door opening (40mm)	Each	8		
<b>Venue : Resource Centre (Lower Level)</b>					
1	Uplifting of existing carpet tiles	M <sup>2</sup>	193.8		
2	Removal of all skirting and quadrants	M	119.70		
3	Removal of carpet tile adhesive from floors in order to obtain level and clean substrate which is conducive to laying of the new laminate flooring.	M <sup>2</sup>	193.8		
4	Prepare the existing floor to receive new floor covering	M <sup>2</sup>	193.8		
5	Installation of vinyl laminate flooring (10mm, Industrial class 32 commercial grade with AC4 wear resistance) (Colour to be selected upon award)	M <sup>2</sup>	193.8		
6	Removal of existing skirting	M	119.70		
7	Installation of 70mm pine skirting. Skirting to be applied x2 coats of varnish (Colour to be discussed upon award)	M	119.70		
8	Removal of existing quadrant	M	119.70		
9	Installation of new 16mm pine quadrant. Quadrant to be varnished (Colour to be discussed upon award)	M	119.70		
10	Trimming of doors to meet floor level	Each	4		
11	Installation of aluminium reducer in door opening (40mm)	Each	4m		
12	Carting away of Rubble	Item	1		

A MANDATORY SITE VISIT WILL BE REQUIRED FOR THE ABOVE QUOTATION REQUEST.



higher education  
& training

Department:  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY**  
**TVET COLLEGE**

W Nombembe

  
Procurement Department

DATE

02/11/2022

S Xokwe

  
Head of Admin

DATE

02/11/2022

S Jane

  
Campus Manager

DATE

02.11.2022

B Timothy

  
SCM Manager

DATE

02-11-2022