



higher education
& training
Department
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



BUFFALO CITY
TVET COLLEGE

REQUEST FOR QUOTATIONS – ABLUTION FACILITIES AT EAST LONDON CAMPUS

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to quotations@bccollege.co.za.

TENDERERS MUST NOTE THAT WHEREVER THIS DOCUMENT REFERS TO ANY PARTICULAR TRADE MARK, NAME, PATENT, DESIGN, TYPE, SPECIFIC ORIGIN OR PRODUCER, SUCH REFERENCE SHALL BE DEEMED TO BE ACCOMPANIED BY THE WORDS 'OR EQUIVALENT.

Kindly submit the following **REQUIRED** documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Latest declaration forms (SBD 4, 8 and 9), see attached on college website
- Certified BBBEE certificate (0 points will be awarded for BBBEE certificates that are not certified)
- Tax Clearance Certificate
- CSD full report
- Company Registration
- Bank Confirmation Letter (not older than 3 months)
- Quotations must be detailed as per specification
- CIDB grading of 1GB or higher (Attach proof)
- **Quotations must be submitted in the PDF format ONLY**
- All quotations submitted via email addresses other than the one listed above will not be considered.

Compulsory Briefing Session: 01 November 2023 @ 14h00 at the East London Campus Hall

Closing Date 07 November 2023 at 11h00 am. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED

043 704 9238 / 043 704 9241



**higher education
& training**

Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY
TVET COLLEGE**

Date: 23 October 2023

Enquiries: nngxekana@bccollege.co.za

CIDB Grading : 1GB or higher may apply

Ablution facilities at East London Campus

Buffalo City TVET College hereby requests qualifying contractors to price as per the following specifications for the Buffalo City TVET College East London Campus ablution facilities revamping.

Please see below specifications:

Number	Item	Description	Unit	Quantity
C – Block (Next to Sim 4 Ground floor) – Female Toilet				
1	Toilet	Remove the existing toilet pans and replace with junior flush master water closet	Each	2
2	Plumbing fittings	Remove the existing water supply piping & fittings, supply and install 22mm copper piping with accessories such as elbows, t pieces e.t.c!	Item	1
3	Painting	Prepare the existing walls to receive x2 coats of fresh paint. Apply two coats of premium quality primer and two coats of premium quality PVA (colour scheme to be chosen upon award)	M ²	33
A- Block (Ground floor) – Female Toilet				
4	Flooring	Remove the existing tiles, prepare area to receive new tiles and retile area. (Replace with tiles at a rate of R180m ²)(Tile only)	M ²	40
5	Cistern Tank	Remove the existing damaged cistern tanks and replace with new similar tanks	Each	5
6	Flushing mechanisms	Remove the existing flushing mechanisms and replace with new high traffic/ heavy duty flushing mechanisms	Each	9

7	Toilet seats	Remove the existing toilet seats and replace with new heavy duty wooden seas (white)	Each	9
8	Toilet paper dispenser	Remove the existing toilet paper and replace with heavy duty metal toilet paper dispenser.	Each	9
A – Block – Disabled Toilet				
9	Flushing mechanism	Remove the existing flushing mechanisms and replace with new high traffic/ heavy duty flushing mechanisms	Each	1
10	Painting	Prepare the existing walls to receive x2 coats of fresh paint. Apply two coats of premium quality primer and two coats of premium quality PVA (colour scheme to be chosen upon award)	M ²	47
A – Block – Male toilets				
11	Flooring	Remove the existing tiles, prepare area to receive new tiles and retile area. (Replace with tiles at a rate of R180m ²)(Tile only)	M ²	27
12	Flushing mechanism	Remove the existing flushing mechanisms and replace with new high traffic/ heavy duty flushing mechanisms	Each	4
13	Toilet seat	Remove the existing toilet seats and replace with new heavy duty wooden seas (white)	Each	4
14	Cistern tank	Remove the existing damaged cistern tanks and replace with new similar tank	Each	1
15	Urinal	Remove the existing urinal and install high traffic adult urinals complete with new traps and piping up to 8 meters in length.	Each	3
16	Tap	Remove and replace 15mm tap with similar	Each	1
17	Trap	Remove the existing sink traps and replace with new rubber traps	Each	6
18	Door Handle	Remove the existing main door handle and replace with new complete three lever lockset	Each	1

A – Block – A108 (left from front entrance)				
19	Basins	Remove the existing basins and replace with new similar size and type of basins	Each	3
20	Stop corks	Installation of 15mm stop corks onto existing supply	Each	3
21	Cistern tanks	Remove the existing damaged cistern tanks and replace with new similar tank	Each	4
22	Flushing mechanism	Remove the existing flushing mechanisms and replace with new high traffic/ heavy duty flushing mechanisms	Each	4
23	Painting (wall)	Prepare the existing walls (above tiles) to receive x2 coats of fresh paint. Apply two coats of premium quality primer and two coats of premium quality PVA (colour scheme to be chosen upon award)	M ²	23
24	Painting (Ceiling)	Prepare the ceilings to receive x2 coats of fresh paint. Apply two coats of premium quality primer and two coats of premium quality PVA (white)	M ²	10.5
A – Block next to A108				
25	Flushing mechanism	Remove the existing flushing mechanisms and replace with new high traffic/ heavy duty flushing mechanisms	Each	2
26	Taps	Remove and replace 15mm tap with similar	Each	2
27	Toilet paper dispenser	Remove the existing toilet paper and replace with heavy duty metal toilet paper dispenser.	Each	2
28	Paper towel holder	Remove the existing paper towel and replace with heavy duty metal toilet paper dispenser.	Each	1
28	Hand dryer	Remove and replace the electric hand dryer and installation of an isolator	Each	1
A – Block – A106				
29	Flushing mechanism	Remove the existing flushing mechanisms and replace with new	Each	1

		high traffic/ heavy duty flushing mechanisms		
30	Pan connector	Remove the existing pan connector and replace with new pan connector	Each	1
31	Toilet seat	Remove the existing toilet seat and replace with new wooden heavy duty toilet seat.	Each	1
32	Paper towel holder	Remove the existing paper towel and replace with heavy duty metal toilet paper dispenser.	Each	1
B – Block – Ground floor (Male Lecture Toilet) (B102)				
33	Toilet	Remove the existing toilet pans and replace with junior flush master water closet	Each	1
34	Plumbing fittings	Remove the existing water supply piping & fittings, supply and install 22mm copper piping with accessories such as elbows, T-pieces e.t.c!	Item	1
35	Urinal	Remove the existing urinal and install high traffic adult urinals complete with new trap and piping up to 8 meters in length.	Each	1
36	Basins	Remove the existing basins and replace with new similar size and type of basins	Each	1
37	Hand dryer	Remove and replace the electric hand dryer and installation of an isolator	Each	1
38	Paper towel holder	Remove the existing paper towel and replace with heavy duty metal toilet paper dispenser.	Each	1
39	Flooring	Remove the existing floor covering, prepare area to receive new tiling. Tiling to be at a rate of R180/m ² . (tile only)	M ²	8
40	Skirting	Remove any fittings or existing skirting's and install a 70mm high	M	15
41	Painting (walls)	Prepare the existing walls to receive fresh paint. Apply two	M ²	61.5

		coats of premium plaster primer and two coats of premium PVA		
42	Painting (Ceilings)	Prepare the existing ceilings to receive fresh paint. Apply two coats of premium primer and two coats of premium ceiling paint	M ²	8
B101 – Female Lecture Toilet				
44	Basin with vanity	Remove the existing vanity and basin (complete with taps, traps etc) and replace with a 1100 x 920 x540mm white melamine cupboard.	Item	1
45	Backsplash tiling	Remove the existing tiling/ mosaic and install new mosaic	M ²	1
46	Flooring	Remove the existing floor covering, prepare area to receive new tiling. Tiling to be at a rate of R180/m ² . (tile only)	M ²	15
47	Toilet	Remove the existing toilet pans and replace with junior flush master water closet	Each	3
48	Plumbing fittings	Remove the existing water supply piping & fittings, supply and install 22mm copper piping with accessories such as elbows, t pieces e.t.c!	Item	1
49	Toilet paper holders	Remove the existing toilet paper holder and replace with new heavy duty metal holders	Each	3
50	Hand dryer	Remove the existing hand dryer and replace with new electric hand dryer and isolator	Each	1
51	Paper towel holder	Remove the existing paper towel and replace with heavy duty metal toilet paper dispenser.	Each	1



N Ngxekana

Project Manager: Infrastructure

Date: 23/10/2023



Z. Chofa
DP: Corporate Services

Date: 24/10/2023



Z. Jikwana
Acting A.D : SCM

Date: 26/10/2023