



higher education  
& training  
Department  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY**  
**TVET COLLEGE**

## **REQUEST FOR QUOTATIONS – SUPPLY AND INSTALLATION OF ABLUTION FACILITIES AT JKB**

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to [quotations@bccollege.co.za](mailto:quotations@bccollege.co.za).

**TENDERERS MUST NOTE THAT WHEREVER THIS DOCUMENT REFERS TO ANY PARTICULAR TRADE MARK, NAME, PATENT, DESIGN, TYPE, SPECIFIC ORIGIN OR PRODUCER, SUCH REFERENCE SHALL BE DEEMED TO BE ACCOMPANIED BY THE WORDS 'OR EQUIVALENT.**

Kindly submit the following **REQUIRED** documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Latest declaration forms (SBD 4, 8 and 9), see attached on college website
- Certified BBBEE certificate (0 points will be awarded for BBBEE certificates that are not certified)
- Tax Clearance Certificate
- CSD full report
- Company Registration
- Bank Confirmation Letter (not older than 3 months)
- CIDB Grading of 1GB or higher (Attach certificate as proof)
- Quotations must be detailed as per specification
- **Quotations must be submitted in the PDF format ONLY**
- All quotations submitted via email addresses other than the one listed above will not be considered.

**Please Note: Compulsory Briefing Session: 06 September 2023 @ 11h00 - John Knox Bokwe**

**Closing Date 08 September 2023 at 11h00 Pm. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED**

043 704 9238 / 043 704 9241

---



higher education  
& training

Department:  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY  
TVET COLLEGE**

Date: 29 August 2023

Enquiries: [nngxekana@bccollege.co.za](mailto:nngxekana@bccollege.co.za)

Delivery Date : (within two week from issuing of purchase order)

All service providers to use this as a pricing document and must submit formal quotes in line with the document below:  
**SPECIFICATION FOR INSTALLATION OF ABLUTION FACILITIES AT JKB**

Number	Item	Scope of works	Unit	Quantity	RATE	TOTAL
<b>Venue 5.5</b>						
1	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"><li>• Disconnect all water supply</li><li>• Remove the existing water closet</li></ul>	Each	2		
2	Installation of WC	<ul style="list-style-type: none"><li>• Installation of a complete junior Flush Master (premium quality to meet heavy traffic use)</li></ul>	Each	2		
3	Painting – Floors	<ul style="list-style-type: none"><li>• All floors to be thoroughly prepared to receive new floor coating</li></ul>	M <sup>2</sup>	34.2		

		<ul style="list-style-type: none"> <li>• Apply two coats of polyurethane on floors as per the recommended factory application</li> </ul>			
4	Painting – Walls	<ul style="list-style-type: none"> <li>• Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>• Apply two coats to an even finish of premium quality similar/ existing colour scheme internal wall paint.</li> </ul>	M <sup>2</sup>	80.64	
5	Painting - Ceilings	<ul style="list-style-type: none"> <li>• Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>• Apply two coats to an even finish of premium quality similar/ existing colour scheme ceiling paint paint.</li> </ul>	M <sup>2</sup>	34.2	

6	Painting – Doors & Trims	<ul style="list-style-type: none"> <li>Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer.</li> <li>Apply two coats of premium white gloss paint.</li> </ul>	Each	4			TOTAL
Number	Item	Scope of works	Unit	Quantity	RATE		
<b>Venue 5.4</b>							
7	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> <li>Disconnect all water supply</li> <li>Remove the existing water closet</li> </ul>	Each	2			
8	Installation of WC	<ul style="list-style-type: none"> <li>Installation of a complete junior Flush Master (premium quality to meet heavy traffic use)</li> </ul>	Each	2			
9	Plumbing: Piping (Venue 5.4 & 5.5)	<ul style="list-style-type: none"> <li>Replace existing copper piping with 22mm Copper</li> </ul>	M	10			
	Elbows	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	10			

	T-Piece	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	4		
	Stop - Cock	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	4		
10	Painting -- Floors	<ul style="list-style-type: none"> <li>All floors to be thoroughly prepared to receive new floor coating</li> <li>Apply two coats of polyurethane on floors as per the recommended factory application</li> </ul>	M <sup>2</sup>	27.36		
11	Painting – Walls	<ul style="list-style-type: none"> <li>Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>Apply two coats to an even finish of premium quality similar/ existing colour scheme internal wall paint.</li> </ul>	M <sup>2</sup>	70.4		
12	Painting - Ceilings	<ul style="list-style-type: none"> <li>Prepare the surface of any cracks and imperfections,</li> </ul>	M <sup>2</sup>	70.4		





	Elbows	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	15		
	T-Piece	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	3		
	Stop - Cock	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	4		
20	Painting – Walls	<ul style="list-style-type: none"> <li>Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>Apply two coats to an even finish of premium quality similar/ existing colour scheme internal wall paint.</li> </ul>	M <sup>2</sup>	24		
21	Painting - Ceilings	<ul style="list-style-type: none"> <li>Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>Apply two coats to an even finish of premium quality similar/ existing</li> </ul>	M <sup>2</sup>	50.7		



		colour scheme ceiling paint paint.							
22	Painting – Doors & Trims	<ul style="list-style-type: none"> <li>Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer.</li> <li>Apply two coats of premium white gloss paint.</li> </ul>	Each	6					
23	Electrical	<ul style="list-style-type: none"> <li>Remove existing electrical light fitting and switch.</li> <li>Install round shaped (no less than 200mm) 6W LED fitting and PVC switch</li> </ul>	Each	4					
<b>Number</b>	<b>Item</b>	<b>Scope of works</b>	<b>Unit</b>	<b>Quantity</b>	<b>RATE</b>	<b>TOTAL</b>			
<b>Venue A2</b>									
24	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> <li>Disconnect all water supply</li> <li>Remove the existing water closet</li> </ul>	Each	6					
25	Installation of WC	<ul style="list-style-type: none"> <li>Installation of a complete junior</li> </ul>	Each	6					

26	Plumbing: Piping	Flush Master (premium quality to meet heavy traffic use)	M	6						
	Elbows	<ul style="list-style-type: none"> <li>Replace existing copper piping with 22mm Copper</li> <li>Replace with 22mm copper</li> </ul>	Each	9						
	T-Piece	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	7						
	Stop - Cock	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	6						
27	Painting – Walls	<ul style="list-style-type: none"> <li>Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>Apply two coats to an even finish of premium quality similar/ existing colour scheme internal wall paint.</li> </ul>	M <sup>2</sup>	54						
28	Painting - Ceilings	<ul style="list-style-type: none"> <li>Prepare the surface of any cracks and imperfections, apply two coats of</li> </ul>	M <sup>2</sup>	50.4						


Number	Item	Scope of works	Unit	Quantity	RATE	TOTAL
29	Painting – Doors & Trims	<ul style="list-style-type: none"> <li>premium quality primer</li> <li>Apply two coats to an even finish of premium quality similar/ existing colour scheme ceiling paint paint.</li> <li>Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer.</li> <li>Apply two coats of premium white gloss paint.</li> </ul>	Each	2		
<b>Venue A1</b>						
30	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> <li>Disconnect all water supply</li> <li>Remove the existing water closet</li> </ul>	Each	8		
31	Installation of WC	<ul style="list-style-type: none"> <li>Installation of a complete junior Flush Master (premium quality</li> </ul>	Each	8		


32	Plumbing: Piping	to meet heavy traffic use)	M	8			
	Elbows	<ul style="list-style-type: none"> <li>Replace existing copper piping with 22mm Copper</li> <li>Replace with 22mm copper</li> </ul>	Each	10			
	T-Piece	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	7			
	Stop - Cock	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	8			
33	Painting – Walls	<ul style="list-style-type: none"> <li>Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>Apply two coats to an even finish of premium quality similar/ existing colour scheme internal wall paint.</li> </ul>	M <sup>2</sup>	50.4			
34	Painting - Ceilings	<ul style="list-style-type: none"> <li>Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> </ul>	M <sup>2</sup>	32			


		<ul style="list-style-type: none"> <li>Apply two coats to an even finish of premium quality similar/ existing colour scheme ceiling paint paint.</li> </ul>				
35	Painting – Doors & Trims	<ul style="list-style-type: none"> <li>Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer.</li> <li>Apply two coats of premium white gloss paint.</li> </ul>	Each	1		
36	Preliminary & General	<ul style="list-style-type: none"> <li>Allow 15 % of total cost of project for P&amp;G</li> </ul>	Item	1		
			<b>Sub total</b>			
			<b>VAT</b>			
			<b>Grand total</b>			

**CIDB GRADING: 1GB or HIGHER (ATTACH CERTIFICATE)**

**A COMPALSORY SITE BRIEFING WILL BE REQUIRED**

N. Ngxekana  
  
30/08/2023  
Project Manager : Facilities Management

Z. Chola  
  
30/08/2023  
DP : Corporate Services

Z. Jikwana  
  
30/08/2023  
Acting A.D : SCM