



higher education
& training
Department
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



BUFFALO CITY
TVET COLLEGE

REQUEST FOR QUOTATIONS

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to quotations@bccollege.co.za ONLY.

TENDERERS MUST NOTE THAT WHEREVER THIS DOCUMENT REFERS TO ANY PARTICULAR TRADE MARK, NAME, PATENT, DESIGN, TYPE, SPECIFIC ORIGIN OR PRODUCER, SUCH REFERENCE SHALL BE DEEMED TO BE ACCOMPANIED BY THE WORDS 'OR EQUIVALENT.

Kindly submit the following **REQUIRED** documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Latest declaration forms (SBD 4, 8 and 9), see attached on college website
- Certified BBBEE certificate (0 points will be awarded for BBBEE certificates that are not certified)
- Tax Clearance Certificate
- CSD full report
- Company Registration document
- CIDB Grading 1GB or higher
- Bank Confirmation Letter (not older than 3 months)
- Quotations must be detailed as per specification
- All quotations submitted via email addresses other than the one listed above will not be considered.

Please Note: Compulsory Briefing Session: 7th August 2023 at 10h00 at East London Campus

Closing Date: 10 August 2023 at 11h00am. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED



**higher education
& training**
Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY
TVET COLLEGE**

Relevant Vocational Education for Changing World

Specification for building alterations at the East London Campus E7 Venue.

For any enquiries: Infrastructure Unit – 043 704 9255 / 043 7049241

Date: 22/06/2023


CIDB GRADING 1GB OR HIGHER (ATTACH THE CERTIFICATE)

Number	Item	Description	Unit	Quantity
1	Dry walling	<ul style="list-style-type: none">Erecting of a 76mm Drywall with 12mm board up to 3.5m in height (18.3m x 3.5m)	M ²	64.5
2	Windows	<ul style="list-style-type: none">Installation of white powder coated aluminum horizontal sliding windowsThe dimension of windows are to be as follows: (1.5 x1.5m)	Each	3
3	Doors	<ul style="list-style-type: none">Installation of white powder coated aluminum modern office doors (813 x 2032)	Each	3
4	Floor covering	<ul style="list-style-type: none">Preparation of existing floors to receive new glue on vinyl flooring (no less than 1200 x 150 x2.5mm). Colour scheme to be chosen upon award by client.	M ²	50
5	Ceilings	<ul style="list-style-type: none">Installation of a new H profile suspended ceiling including aluminum ceiling frame	M ²	50
6	Electrical	<ul style="list-style-type: none">Lights - Supply and install 15AMP breaker onto the nearest DB board with 1.5mm twin and earth from nearest DB (30m), supply	Item	1

		<p>and install light switches & modern round (200mm) LED light fittings to all x3 offices</p> <ul style="list-style-type: none"> • Plug points – Supply and install 20 Amp breaker with 2.5mm twin and earth, supply and install double plug points with USB charging port and 2 pin port to all x3 offices. 	Item	1
7	Painting	<ul style="list-style-type: none"> • Prepare all walls to receive new paint • Apply x2 coats of premium quality under coat • Apply x2 coats of premium quality similar colour paint. • Prepare existing timber door to receive new varnish. Apply two coats of timber oil and x2 coats of existing varnish colour 	M ²	180
			Each	1

N.B: Compulsory Site briefing will be requested.

Mrs N. Ngxekana

 22/06/2023

Project manager- Infrastructure

 27/07/2023

Mr Z Chola

DP: Corporate services

 22/08/2023

Ms Z Jikwana

Acting assistant director: SCM

BUFFALO CITY TVET COLLEGE
Venue E7

