



higher education
& training
Department
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



BUFFALO CITY
TVET COLLEGE

REQUEST FOR QUOTATIONS

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to quotations@bccollege.co.za ONLY.

TENDERERS MUST NOTE THAT WHEREVER THIS DOCUMENT REFERS TO ANY PARTICULAR TRADE MARK, NAME, PATENT, DESIGN, TYPE, SPECIFIC ORIGIN OR PRODUCER, SUCH REFERENCE SHALL BE DEEMED TO BE ACCOMPANIED BY THE WORDS 'OR EQUIVALENT.

Kindly submit the following **REQUIRED** documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Latest declaration forms (SBD 4, 8 and 9), see attached on college website
- Certified BBBEE certificate (0 points will be awarded for BBBEE certificates that are not certified)
- Tax Clearance Certificate
- CSD full report
- Company Registration document
- CIDB Grading 1GB or higher
- Bank Confirmation Letter (not older than 3 months)
- Quotations must be detailed as per specification
- All quotations submitted via email addresses other than the one listed above will not be considered.

Please Note: Compulsory Briefing Session: 10th August 2023 at 11h00 at Gloucester House

Closing Date: 14 August 2023 at 11h00am. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED



**higher education
& training**
Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY
TVET COLLEGE**

Relevant Vocational Education for a Changing World

Supply and Delivery of Pre- fabricated guard house that is to be delivered to Corner of King street and St Marks Road (Gloucester House)


Date: 18 July 2023

No.	Area	Item	Description	Quantity
1.	Gloucester House	Prefab Guard House	<ul style="list-style-type: none">Supply and delivery of a white guard house (No less than 4m²)	4M ²
		Body	<ul style="list-style-type: none">Guard house to be built with either Aluzinc or Chromo deck with insulated panels.	
		Window	<ul style="list-style-type: none">Guard house must be fitted with aluminium window and aluminium security bars	
		Door	<ul style="list-style-type: none">Guard house to be fitted with glue on vinyl flooring.	
		Flooring covering	<ul style="list-style-type: none">Guard house to be fitted with glue on vinyl flooring.	
		Roofing	<ul style="list-style-type: none">Guard house roofing to be built with IBR galvanised zinc,PVC barge & fascia boards	

			aluminium gutters and down pipes.	
		Electrical	<ul style="list-style-type: none"> Guard house must come fitted with a sub DB board comprising of x 1 main breaker, x1 earth leakage, x1 light fitting breaker, x1 plug point breaker. Sub DB must be ready to receive electrical supply and to distribute to installed x1 electrical plug,x1 electrical switch and x1 Led light. All cabling and accessories to be ran neatly behind trunking. 	

Mrs N. Ngxekana

Project manager- Infrastructure




Mr Z Chola

DP: Corporate services



Mrs Z Jikwana

Acting assistant director: SCM

 02/08/2013