



higher education  
& training  
Department  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY**  
**TVET COLLEGE**

**REQUEST FOR QUOTATIONS – RENOVATIONS FOR TRANSPORT OFFICE**  
**AT EAST LONDON CAMPUS**

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to [quotations@bccollege.co.za](mailto:quotations@bccollege.co.za).

**TENDERERS MUST NOTE THAT WHEREVER THIS DOCUMENT REFERS TO ANY PARTICULAR TRADE MARK, NAME, PATENT, DESIGN, TYPE, SPECIFIC ORIGIN OR PRODUCER, SUCH REFERENCE SHALL BE DEEMED TO BE ACCOMPANIED BY THE WORDS 'OR EQUIVALENT.**

Kindly submit the following **REQUIRED** documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Latest declaration forms (SBD 4, 8 and 9), see attached on college website
- Certified BBBEE certificate (0 points will be awarded for BBBEE certificates that are not certified)
- Tax Clearance Certificate
- CSD full report
- Company Registration
- Bank Confirmation Letter (not older than 3 months)
- Quotations must be detailed as per specification
- CIDB grading of 1GB or higher (Attach proof)
- **Quotations must be submitted in the PDF format ONLY**
- All quotations submitted via email addresses other than the one listed above will not be considered.

**Compulsory briefing session: 09 November 2023 @11h00 at East London Campus.**

**Closing Date 15 November 2023 at 11h00 am. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED**

043 704 9238 / 043 704 9241

---



**higher education  
& training**  
Department:  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY  
TVET COLLEGE**

Relevant Vocational Education for Changing World

**RENOVATION OF TRANSPORT OFFICE EAST LONDON CAMPUS**

Requires. CIDB-1GB or Higher


Enquiries: [nngxekana@bccollege.co.za](mailto:nngxekana@bccollege.co.za)

Date: 31 October 2023

NO	ITEM	DESCRIPTION	UNIT MEASURE	QUANTITY
1.	Painting	Prepare the walls and ceiling to a smooth finish and apply three coats of high quality interior matt finish (same as existing colour) to a smooth finish.	M <sup>2</sup>	140
		Apply dump sealer in to the dump area	M <sup>2</sup>	54.96
2.	Floor	Remove existing floor rug	M <sup>2</sup>	18
		Install new under floor heating	M <sup>2</sup>	28
		Install new Burberry beige polished porcelain tile	M <sup>2</sup>	28
		Install new 75mm aluminium skirting	M	36
		Installation of Rubber on the stairs	No	3
3.	Electricity	Install three electric wall box for plugs	No	3
		Electric wire must run in trunking case of 20mm run in top of the skirting	M	12
		Double Plugs must be in a wall box and be mounted to the wall	No	3
		Remove the existing lights and install new LED lights .	No	4
		Install new 12000 BTU air conditioner	No	1
4.	Plumbing	Remove existing water pipes for showers.	No	1
		Remove the existing water channels	M	2
		Remove old shower trap and install new trap.	No	1
		Installation of new ceramic tile	M <sup>2</sup>	3
		Installation new cobra junior mix flush system.	No	1
		Installation new 100 litre geyser wall mounted.	No	1
		Install 400 diameter hand basin including water inlet with a water mix tap and cobra junior trap and outlet	No	1

		Install new 500mmx 600mm mounted mirror	No	1
		Install new soap holder mounted to the wall inside the shower	No	1
		Finish us with compliance certificate for air condition and geyser	No	2
5.	Doors	Prepare doors to receive paint and apply three coat of gloss paint	No	3
6	COC	Issuing of COC certificate after completion of work.	Item	1

N. Ngxekana

  
Project manager

31/10/2023

Z. Chola

  
DP: Corporate Services

01/11/2023

Z. Jikwana

  
Acting A.D : SCM

06/11/2023