



higher education
& training
Department
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



BUFFALO CITY
TVET COLLEGE

REQUEST FOR QUOTATIONS – MINOR REPAIRS AND MAINTENANCE AT GLOUCESTER HOUSE

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to quotations@bccollege.co.za.

TENDERERS MUST NOTE THAT WHEREVER THIS DOCUMENT REFERS TO ANY PARTICULAR TRADE MARK, NAME, PATENT, DESIGN, TYPE, SPECIFIC ORIGIN OR PRODUCER, SUCH REFERENCE SHALL BE DEEMED TO BE ACCOMPANIED BY THE WORDS 'OR EQUIVALENT.

Kindly submit the following **REQUIRED** documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Latest declaration forms (SBD 4, 8 and 9), see attached on college website
- Certified BBBEE certificate (0 points will be awarded for BBBEE certificates that are not certified)
- Tax Clearance Certificate
- CSD full report
- Company Registration
- Bank Confirmation Letter (not older than 3 months)
- Quotations must be detailed as per specification
- CIDB grading of 1GB or higher (Attach proof)
- **Quotations must be submitted in the PDF format ONLY**
- All quotations submitted via email addresses other than the one listed above will not be considered.

Compulsory briefing session: 09 November 2023 @10h00 at Gloucester House.

Closing Date 15 November 2023 at 11h00 am. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED

043 704 9238 / 043 704 9241



higher education
& training

Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



BUFFALO CITY
TVET COLLEGE

Date: 31 October 2023

Enquiries: nngxekana@bccollege.co.za

MINOR REPAIRS AND MAINTENANCE FOR GLOUCESTER HOUSE

Buffalo City TVET College hereby request a priced quotation from suitable contractors for the **Minor repairs and maintenance for Gloucester House**. Contractors whom are registered with the CIDB Grade 1GB or higher registration may apply (attach the certificate).


Number	Item	Description	Unit	Quantity
1.	Painting of internally walls. (Main Building)	<ul style="list-style-type: none">Prepare the wall and apply three coats of high quality interior matt finish (same as existing colour) to a smooth finish.	M2	100
2.	Painting Internally all Bathrooms.(Main Building)	<ul style="list-style-type: none">Prepare the wall and apply three coats of high quality premium aqua velvet pastel.	M2	60
3.	Painting (Ceilings Main Building)	<ul style="list-style-type: none">Prepare ceiling and ply two coats premium primer.Apply two coats of premium white paint of ceilings.	M2	50
4	Front door (Main Building)	<ul style="list-style-type: none">Remove and install new aluminum door including the necessary accessories.	Item	1
5	Door	<ul style="list-style-type: none">Replace existing normal door for external use (Standard door size including door lock set with handle.)	Item	2
6	Passage and Room F2	<ul style="list-style-type: none">Repair ceiling with existing material and apply three coats of paint.	M2	8

7.	Cleaning of Aluminum windows	<ul style="list-style-type: none"> • Cleaning of Aluminum windows and allowance of hiring Scaffolding for high heights. 	No	56
8.	Cleaning of Steel windows	<ul style="list-style-type: none"> • Cleaning of Steel windows and allowance of hiring Scaffolding for high heights. 	No	62
9	Light Bulb F10,Bathroom 1,	<ul style="list-style-type: none"> • Replacement of existing light bulb 	No	1
10.	Bathroom 1	<ul style="list-style-type: none"> • Remove and install shower heads set and arms. 	No	4
	Bathroom 1	<ul style="list-style-type: none"> • Supply and install Toilet flushing Cistern white including internal flushing mechanism and flush pipe. 	No	1
11.	Bathroom 2	<ul style="list-style-type: none"> • Supply and install sink star silver pillar tap. 	No	4
		<ul style="list-style-type: none"> • Remove and install shower heads set and arms. 	No	2
		<ul style="list-style-type: none"> • Supply and install Toilet flushing Cistern white including internal flushing mechanism and flush pipe. 	No	1
12.	Bathroom 3	<ul style="list-style-type: none"> • Remove and install shower heads set and arms. 	No	2
		<ul style="list-style-type: none"> • Remove and install star silver tap for showers 	No	2
		<ul style="list-style-type: none"> • Apply two coats of premium white paint of ceilings. 	M2	20
13.	EXTERNAL HOUSE (Passage,	<ul style="list-style-type: none"> • Prepare the wall and apply three coats of high quality interior 	M2	320

	Laundry and rooms)	matt finish (same as existing colour) to a smooth finish.		
		<ul style="list-style-type: none"> Apply two coats of premium white paint of ceilings @ Laundry area 	M2	9
14.	Ablutions (External House)	<ul style="list-style-type: none"> Supply and Install Coral white Top fit Toilet seat pans. 	No	2
15.	Glazing	<ul style="list-style-type: none"> Installation new glazing for broken windows. 	M2	2
16.	EXTERNAL BUILDING	<ul style="list-style-type: none"> Prepare the wall and apply three coats of high quality interior matt finish (same as existing colour) to a smooth finish. 	M2	270
17.	BARTHROOMS EXTERNAL	<ul style="list-style-type: none"> Prepare the wall and apply three coats of high quality premium aqua velvet pastel. 	M2	40
18.	PAINTING CEILINGS	<ul style="list-style-type: none"> Apply two coats of premium white paint for the ceilings. 	M2	24
19.	LAUNDRY ROOM	<ul style="list-style-type: none"> Supply & install white PVC 160mm drainage pipe. 	m	6.5
		<ul style="list-style-type: none"> Supply & install 90 degree bends with eye opening (40 mm) 	Each	2
		<ul style="list-style-type: none"> Supply & install T-piece bends (40 mm) 	Each	4
		<ul style="list-style-type: none"> Supply & install pipe bidding/holder per 400mm. 	Each	12
		<ul style="list-style-type: none"> Install 15mm T piece from outside mall, drill opening to run 15mm pipe inside the venue, run 15mm copper pipe. 	Item	1
		<ul style="list-style-type: none"> Install 15mm stainless still taps 	Item	1

20	Electrical work	<ul style="list-style-type: none"> Supply and install twin and earth from existing plug point (4 mm). All cabling to be run neatly inside applicable conduct pipe. Ensure to neatly close off existing plus point. 	m	12
		<ul style="list-style-type: none"> Supply & install three pin plug points. All to be surface mounted. 	Each	5
21	Passage House 2	<ul style="list-style-type: none"> Remove and prepare the existing matt and install new vinyl tiles. 	M2	8
		<ul style="list-style-type: none"> Install rubber cover strips on steps. 	m	15
		<ul style="list-style-type: none"> Apply varnish into skirting. 	m	42
22	Shower Curtains	<ul style="list-style-type: none"> 1.00 m and 1.90 length shower curtain fabric. 	No	22

N. Ngxekana

 31/10/2023

Project manager

Z. Chola


DP: Corporate Services

Z. Jikwara

 06/11/2023
Acting A.D : SCM