



## REQUEST FOR QUOTATION: MAINTANCE OF TOILET FACILITIES AT STM CAMPUS

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to weziwe@bccollege.co.za; cc: zimkhitha@bccollege.co.za

Kindly submit the following REQUIRED documents when responding to the RFQ

- Signed quotation ( quotations not signed will be eliminated)
- Declaration forms (SBD 4, 8 and 9)
- Certified BEE certificate ( 0 points will be awarded for BEE certificates that are not certified)
- Tax Clearance Certificate
- CSD report
- Bank Confirmation Letter (not older than 3 months)

Closing Date: 23 February 2022 at 11h00 am. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED

Enquiries: Ms Weziwe Gwabavu / Zimkhitha Jikwana 043 704 9241





Specification for the maintenance of toilet facilities at St Marks Campus

Enquiry: nngxekana@bccollege.co.za

Date: 03/02/2022

No _	Item	Description	Unit	Quantity
Show	ver			
1.	Building	Erect a 1800 x 2000 mm single brick wall by means of 110mm plaster brick.	M <sup>2</sup>	3.6
		<ul> <li>All building works to comply with the NHBRC standards.</li> </ul>		
2	Plastering	Plaster newly erected wall on both sides with a 15mm thick motar mix	M <sup>2</sup>	7.2
	Tiling	Tile both walls by using existing wall tiles	M <sup>2</sup>	7.2
Wate	r closet			
3	Toilet	Remove existing water closet pan.	No	6
		Install new complete Cobra junior flush master system with white Cobra ceramic toilet pan.	No	1
Door:	5			
4	Doors	Remove existing door and door frame.		
		install new standard meranti door frame and door with a three lever union locking system.	No.	1
Urina	ais			
5	Urinal basin	Re-amount the existing "Man's" urinal basin.	No	12
		Install new Cobra junior flushing system in urinal basins	No	12
		Remove existing drainage outlets traps.		
		Install new PVC outlet drainage traps	No	12
Wate	r closet			
6	Flush system	Remove all existing flush system in place	No	18
		Install new complete Cobra junior flush master system (with strainer) with white Cobra ceramic toilet pan.	NO	18
		Pressure control valves to be installed where applicable	Item	1
		Check the existing water pressure in place and put the necessary measures to accommodate the new flush system	No	1
7	Finish	Finish all working area in a good condition and neatness ( if the paint is affected re-paint with	Item	1

same colour if the tile is broken re-place It		
neatly)	<u></u>	

The specification must be submitted to the SCM office with the following document

- 1. Company registration
- 2. BEE Certificate
- 3. Tax clearance certificate
- 4. SBD 4.8.9 Form
- 5. Proof of CSD registration

## **CIDB Grading**

• 1GB PE or higher may apply.

N.B a compulsory site visit must take place, details will be communicated by the SCM department.

N. Ngxekana

A.D : Infrastructure

حرZ.Chg

DP : Corporate Services

S.Siwisa

A.D : Infrastructure SCM

Date: 15/02/2022