



higher education  
& training  
Department  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY**  
**TVET COLLEGE**

### **REQUEST FOR QUOTATION: WI- FI INSTALLATION**

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to [quotations@bccollege.co.za](mailto:quotations@bccollege.co.za)

Kindly submit the following **REQUIRED** documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Declaration forms (SBD 4, 8 and 9)
- Certified BEE certificate (0 points will be awarded for BEE certificates that are not certified)
- Tax Clearance Certificate
- CSD report
- Bank Confirmation Letter (not older than 3 months)

**N. B. Compulsory site briefing session will be held at East London Campus on Friday 01 April 2022 @ 09 Am.**

**Closing Date: 08 April 2022 at 11:00 Am. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED**

Enquiries: Ms Weziwe Gwabavu / Zimkhitha Jikwana

043 704 9241

---



higher education  
& training

Department  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY**  
**TVET COLLEGE**

To: Whom It May Concern

Date: 11.03.2022

**Request for Wi-Fi installation in JKB, EL, KS and STM campuses**

Buffalo City Campus invites all suitable and qualified service providers to submit their quotations for the following Buffalo City TVET College Supply, delivery and installation Cat 6A network points with Fibre links as indicated in the scope of work, mounting of Meraki indoors and outdoors APs to JKB, EL, KS and STM campuses.

- All Service providers must quote according to the specification.
- All Service providers must submit accreditation of at least two certificates of data cabling standardization such as MOLEX, KRONE AND ATTAC.
- All Service providers must submit one certificate of Fiber.
- All service providers must attend Site visit and it is compulsory.
- Delivery date must be within 2 weeks of the issuing of an official purchase order

**Scope of work**

JKB CAMPUS		
No	DESCRIPTION	QTY
1	Network points cat 6A	20
2	Fly leads cat 6A	20
3	Patch leads cat 6A	20
4	Patch panels cat6 A 24 Port	6
5	Fibre Single Mode Hd Micro fibre 12 core	600m
6	4 way duct 1410 and danger tape	550m
7	Trenching 500mm deep and 200mm wide soft soil	300m
8	Trench 600mm deep and 200mm wide Hard rock	25m
9	Hot Tar supply and install	25m
10	man holes p400	2
11	length of Bosal Steel pipe 50mil and couplings saddles	20m
12	bosal pipe adaptor	5
13	Draw Box J2	5
14	Length 16 x 40 PVC Trunking	45m
15	Mount AP indoor and outdoor Cisco Meraki	20
16	SFP single mode 10gig Cisco Meraki	16
17	Fibre Leads 3m Duplex Single mode LC to LC	16
	12 U cabinet complete with 2 fans 5-way power swing Frame 600 deep	5

**ADMIN CENTRE**

Corner Lukin & King Streets  
Private Bag 9016  
East London, 5200  
Tel: (043) 722 5453  
Fax: (043) 704 9274  
Email: ceo@bccollege.co.za

**COLLEGE CAMPUSES**

**EAST LONDON**

Lukin Road, East London  
Private Bag 9016  
East London, 5200  
Tel: (043) 722 5453  
Fax: (043) 743 0116  
Email: elcadmin@bccollege.co.za

**JOHN KNOX BOKWE**

Mfaca Street, Nu1, Mdantsane  
Private Bag X24  
Mdantsane, 5219  
Tel: (043) 781 1782  
Fax: (043) 761 4803  
Email: jkbadmin@bccollege.co.za

**ST MARKS**

St Marks Road, East London  
Private Bag 9016  
East London, 5200  
Tel: (043) 743 6554  
Fax: (043) 743 9650  
Email: stmadmin@bccollege.co.za

**BUSINESS SKILLS CENTRE**

Lukin Road, East London, 5200  
Tel: (043) 743 2810  
Fax: (043) 743 6772  
Email: bskills@bccollege.co.za

**Scope of work**

<b>EL CAMPUS</b>		
	<b>DESCRIPTION</b>	<b>QTY</b>
1	Network Points cat 6A	20
2	Fly leads cat 6A	20
3	Patch Leads cat 6A	20
4	Patch panels cat 6A	5
5	Length Trunking 16 x 40 pvc	60m
6	Mount AP Cisco Meraki outdoor and indoor	20
7	Fibre Single Mode Hd Micro fibre 12 core	600m
<b>STM CAMPUS AND KSS</b>		
1	Network Points cat 6A	20
2	Fly Leads cat 6A	20
3	Patch Leads cat 6A	20
4	Patch panels 24 port cat 6A	5
5	Length bosal steel pipe 50 mil saddles couplings	15m
6	Draw box J2	5
7	Adaptors 50 mil bosal steel pipe	5
8	Trench soft rock from workshop to Prefabs	20m
9	Mount AP indoor and outdoor Cisco Meraki	20

  
Mr. M. Davani  
Chief Network Controller

  
Mr. S. Joseph  
Assistant Director ICT

  
Mrs. S. Siwisa  
SCM: Assistant Director