



higher education
& training
Department
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



BUFFALO CITY
TVET COLLEGE

REQUEST FOR QUOTATION: SUPPLY AND INSTALL CERAMIC TILES

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to weziwe@bccollege.co.za; cc: zimkhitha@bccollege.co.za

Kindly submit the following **REQUIRED** documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Declaration forms (SBD 4, 8 and 9)
- Certified BEE certificate (0 points will be awarded for BEE certificates that are not certified)
- Tax Clearance Certificate
- CSD report
- Bank Confirmation Letter (not older than 3 months)

N.B .Compulsory site briefing will be held on 16 March 2022 @ 12 Am;

Address: Mfafa Street (John Knox Bokwe Campus)

Mdantsane

East London

5201

Closing Date: 23 March 2022 at 12h00 am. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED

Enquiries: Ms Weziwe Gwabavu / Zimkhitha Jikwana

043 704 9241



**higher education
& training**

Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY
TVET COLLEGE**

Date: 04/02/2022

To whom it may concern

RE: Quotation request for placement of ceramic tiles in the admin passage staff toilets male and female, in the staffroom male and female toilets including passage leading to staffroom kitchen and lastly the visitors male and female toilets in the administration block at the J K B Campus.

ITEM	DESCRIPTION AND REQUIRMENTS
1	Initially I forward the square meterage of venues which require an upgrade from vinyl floor tiles to ceramic tiles 300 x 300 mm with off white been the preferred colour and dove grey grouting.
	Male toilet admin passage 3.55 m2
	Female toilet admin passage 3.55 m2
	Visitors female toilet 4.00 m2
	Visitors male toilet 5.55 m2
	Staff kitchen and inter leading passage 10.43 m2
	Male staff toilet 4.83 m2
	Female staff toilet 5.36 m2
	Total square meterage 37.27 m2
2	All of the above venues inclusive of square meterage require the following procedures to be followed.
3	Remove skirting and quadrant.
4	Removal of vinyl tiles.
5	Removal of vinyl tile adhesive from floor.
6	In the event of un-even floor a screed will be required to be applied and sanded to obtain a level base prior to the application of the ceramic tiles.
7	Application of ceramic floor tiles
8	On completion and once tile adhesive has set grouting to be applied dove grey is the colour required.
9	On completion of the tiling and grouting skirting and quadrant to be replaced in the event of any breakages replace with new prime and paint to the existing colour.
10	On completion of the above tiling task all replaced vinyl tiles and builders rubble to be removed off site.

A MANDATORY SITE VISIT WILL BE REQUIRED FOR THE ABOVE MENTIONED UPGRADE


Mr W Nonyembembe
Procurement Department

Date 04/02/2022


Ms S Xokwe
Head of Admin

Date 04/02/2022


Mr. S Mbiza
Acting Campus Manager

Date 04/02/2022



higher education
& training

Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY
TVET COLLEGE**


Mr P Mawla
DP: Academic

Date 07/02/2022


Mrs S Shwisa
Assist Director: SCM

Date 09/03/2022