



higher education
& training
Department
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



BUFFALO CITY
TVET COLLEGE

REQUEST FOR QUOTATIONS AND SITE BRIEFING FOR INSTALLATION OF ABLUTION FACILITIES

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to quotations@bccollege.co.za

Kindly submit the following **REQUIRED** documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Declaration forms (SBD 4, 8 and 9)
- Certified BEE certificate (0 points will be awarded for BEE certificates that are not certified)
- Tax Clearance Certificate
- CSD report
- Bank Confirmation Letter (not older than 3 months)

N. B. Compulsory site briefing session will be held at King Street Campus on Friday 13 May 2022 @ 09 Am.

Closing Date: 20 May 2022 at 11:00 Am. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED

Enquiries: Ms Weziwe Gwabavu / Zimkhitha Jikwana

043 704 9241



To : Whom it may concern

From : Buffalo City TVET College

Subject : Request for price quotation

Delivery: After purchase order issued project will take four weeks for completion.

Kindly submit a priced quotation for the installation of ablution facilities at King Street and Belgravia Soot Classroom Ablutions

King Street Ablutions

No	ITEM	Unit	QTY	SCOPE OF WORK
Male Toilet Venue 19				
1	Door	Each	2	<ul style="list-style-type: none"> Remove existing timber hollow doors Install new timber internal hollow doors Apply two coats of premium timber primer Apply two coats of premium white door & trims gloss/ oil paint Doors to be fitted with 2 lever premium quality handle and lock.
2	Water Closet	Each	2	<ul style="list-style-type: none"> Remove the existing toilet pans Installation of new premium quality Junior Flush Master
3	Hand Basins	Each	2	<ul style="list-style-type: none"> Remove the existing hand basins Installation of new similar sized hand basins, mounted onto wall with heavy duty brackets (no pedestal) (Premium quality)
4	Urinals	Each	2	<ul style="list-style-type: none"> Remove the existing 1.5m urinal Installation of two separate junior flush master urinals
5	Plumbing : Piping	M	15	<ul style="list-style-type: none"> Remove the existing 15mm piping Upgrade water supply to 22mm copper piping. All pipes to be ran on the surface with biddings.
	Elbows	Each	4	<ul style="list-style-type: none"> Replace with 22mm Brass
	T-Piece	Each	2	<ul style="list-style-type: none"> Replace with 22mm Brass
	Stop Cock	Each	4	<ul style="list-style-type: none"> Install on each water closet (22mm)



6	Window	Each	1	<ul style="list-style-type: none"> Remove the existing steel case window frame and install a new 1000mm x 700mm aluminium window frame.
Female Toilet External (Ground Floor)				
7	Painting	M ²	60.9	<ul style="list-style-type: none"> Prepare the existing gloss finished surface to receive new PVA paint Apply three coats of premium primer Apply three coats of premium grey PVA paint
8	Water closets	Each	4	<ul style="list-style-type: none"> Remove the existing toilet pans Installation of new premium quality Junior Flush Master
9	Plumbing : Piping	M	20	<ul style="list-style-type: none"> Remove the existing 15mm piping Upgrade water supply to 22mm copper piping. All pipes to be ran on the surface with biddings.
	Elbows	Each	3	<ul style="list-style-type: none"> Replace existing with 22mm brass
	T-Piece	Each	2	<ul style="list-style-type: none"> Replace existing with 22mm brass
	Stop cock	Each	5	<ul style="list-style-type: none"> Install on each water closet (22mm)
10	Door	Each	2	<ul style="list-style-type: none"> Remove the existing custom made melamine doors Install new melamine doors, as per the existing dimensions All doors to be machined edged with 2mm PVC edging All doors to be fitted with existing (Vacant/ busy) locking devices
11	Wall linings	M ²	1	<ul style="list-style-type: none"> Attend to damaged wall lining and replace with new similar colour scheme wall vinyl lining.



12	Flooring	M ²	18.9	<ul style="list-style-type: none"> Prepare the flooring to receive to receive new tiling, all existing polyurethane floor covering to be scraped off before tiling. Installation of tile @ a rate of R180 per square meter. (cost of tile only)(Tile to be chosen upon awarding with client)
Male Toilet External (Ground Floor)				
13	Urinals	Each	4	<ul style="list-style-type: none"> Remove the existing urinals Install Junior flush Master urinal
14	Plumbing : Piping	M	15	<ul style="list-style-type: none"> Remove the existing 15mm polycop pipe Install 22mm copper piping
	Elbows	Each	6	<ul style="list-style-type: none"> Replace with 22mm brass
	T – Piece	Each	4	<ul style="list-style-type: none"> Replace with 22mm brass
	Stop cork	Each	4	<ul style="list-style-type: none"> Replace with 22mm brass to each water closet
15	Water closet	Each	4	<ul style="list-style-type: none"> Remove the existing toilet pans Installation of new premium quality Junior Flush Master
Internal Workshop passage				
16	Reveals	M ²	2	<ul style="list-style-type: none"> Attend to the damaged reveals Replaster the cracked area Ensure to fix door frame into the reveal
	Painting	2	8	<ul style="list-style-type: none"> Prepare the surface of the wall to receive new painting Apply two coats of premium primer Apply two coats similar colour premium interior paint

King Street Campus

No	ITEM	Unit	QTY	SCOPE OF WORK
----	------	------	-----	---------------



Staff toilet Ground Floor				
17	Water Closet	Each	1	<ul style="list-style-type: none"> Remove the existing toilet pans Installation of new premium quality Junior Flush Master
	Plumbing : Piping	M	2	<ul style="list-style-type: none"> Remove the existing 15mm polycop pipe Install 22mm copper piping
	Elbows	Each	1	<ul style="list-style-type: none"> Replace with 22mm brass
	Stop cork	Each	1	<ul style="list-style-type: none"> Replace with 22mm brass to each water closet
18	Flooring	M ²	3.7	<ul style="list-style-type: none"> Remove the existing vinyl floor covering Prepare surface to receive new ceramic tiling Installation of tile @ a rate of R180 per square meter. (cost of tile only (Tile to be chosen upon awarding with client)
19	Electrical	Each	1	<ul style="list-style-type: none"> Remove the existing light fitting Install new modern round shaped LED light fitting (200mm x 200mm)
Male Ground floor toilet				
20	Water closet	Each	2	<ul style="list-style-type: none"> Remove the existing toilet pans Installation of new premium quality Junior Flush Master
21	Urinal	Each	1	<ul style="list-style-type: none"> Remove existing urinal Install Junior flush master urinal
22	Plumbing : Piping	M	5	<ul style="list-style-type: none"> Remove the existing 15mm piping Upgrade to 22mm copper piping
	Elbows	Each	6	<ul style="list-style-type: none"> Replace with 22mm brass
	Stop cock	Each	3	<ul style="list-style-type: none"> Replace the existing to each water closet and urinal
23	Flooring	M ²	20.64	<ul style="list-style-type: none"> Remove the existing floor covering Prepare surface to receive new ceramic tile Installation of tile @ a rate of R180 per square meter. (cost of tile only (Tile to be chosen upon awarding with client)



Female Ground Floor toilet				
24	Water closet	Each	2	<ul style="list-style-type: none"> Remove the existing toilet pans Installation of new premium quality Junior Flush Master
25	Plumbing : Piping	M	5	<ul style="list-style-type: none"> Remove the existing 15mm piping Upgrade to 22mm copper piping
	Elbows	Each	6	<ul style="list-style-type: none"> Replace with 22mm brass
	Stop cock	Each	2	<ul style="list-style-type: none"> Replace the existing to each water closet
	Flooring	M ²	8.17	<ul style="list-style-type: none"> Remove the existing floor covering Prepare surface to receive new ceramic tile Installation of tile @ a rate of R180 per square meter. (cost of tile only (Tile to be chosen upon awarding with client)
First Floor Toilets B10 & B11				
26	Water closet	Each	2	<ul style="list-style-type: none"> Remove the existing toilet pans Installation of new premium quality Junior Flush Master
	Plumbing : Piping	M	5	<ul style="list-style-type: none"> Remove the existing 15mm piping Upgrade to 22mm copper piping
	Elbows	Each	4	<ul style="list-style-type: none"> Replace with 22mm brass
	Stop cock	Each	2	<ul style="list-style-type: none"> Replace the existing to each water closet
	T-Piece	Each	1	<ul style="list-style-type: none"> Replace with 22mm brass
27	Flooring	M ²	7	<ul style="list-style-type: none"> Remove the existing floor covering Prepare surface to receive new ceramic tile Installation of tile @ a rate of R180 per square meter. (cost of tile only (Tile to be chosen upon awarding with client)
28	Wall	M ²	2	<ul style="list-style-type: none"> Prepare the surface to receive new tiling Installation of tile @ a rate of R180 per square meter. (cost



29	Plumbing : Piping	M	5	<ul style="list-style-type: none">Remove the existing 15mm pipingUpgrade to 22mm copper piping
	Elbows	Each	2	<ul style="list-style-type: none">Replace with 22mm brass
	Stop cock	Each	1	<ul style="list-style-type: none">Replace the existing to each water closet
30	Flooring	M ²	16	<ul style="list-style-type: none">Remove the existing floor coveringPrepare surface to receive new ceramic tileInstallation of tile @ a rate of R180 per square meter. (cost of tile only (Tile to be chosen upon awarding with client)

A compulsory site visit will take place as per the determination of the SCM office, details to be advised by the SCM department.

Kind regards

N.Ngxekana

A.D Infrastructure

Z. Chola

DP : Corporate Services

S. Siwisa

A.D SCM