



higher education  
& training  
Department  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY**  
**TVET COLLEGE**

**REQUEST FOR QUOTATION: REPAIRS AND MAINTANANCE TO TOILET  
FACILITIES (JKB)**

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to [quotations@bccollege.co.za](mailto:quotations@bccollege.co.za)

Kindly submit the following **REQUIRED** documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Declaration forms (SBD 4, 8 and 9)
- Certified BEE certificate (0 points will be awarded for BEE certificates that are not certified)
- Tax Clearance Certificate
- CSD report
- Bank Confirmation Letter (not older than 3 months)
- Quotations must be detailed as the specification

**Closing Date: 20 May 2022 at 10:00 Am. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED**

Enquiries: Ms Weziwe Gwabavu / Zimkhitha Jikwana

043 704 9241

---



higher education  
& training

Department  
Higher Education and Training  
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY**  
**TVET COLLEGE**

Date: 28 April 2022

Enquiries: [nngxekana@bccollege.co.za](mailto:nngxekana@bccollege.co.za)

Delivery Date : (within two week from issuing of purchase order)

**REPAIRS AND MAINTENANCE TO TOILET FACILITIES – JOHN KNOX BOKWE CAMPUS**

Number	Item	Scope of works	Unit	Quantity
<b>Venue 5.5</b>				
1	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"><li>• Disconnect all water supply</li><li>• Remove the existing water closet</li></ul>	Each	2
2	Installation of WC	<ul style="list-style-type: none"><li>• Installation of a complete junior Flush Master (premium quality to meet heavy traffic use)</li></ul>	Each	2
3	Painting – Floors	<ul style="list-style-type: none"><li>• All floors to be thoroughly prepared to receive new floor coating</li><li>• Apply two coats of polyurethane on floors as per the recommended factory application</li></ul>	M <sup>2</sup>	34.2
4	Painting – Walls	<ul style="list-style-type: none"><li>• Prepare the surface of any cracks and imperfections,</li></ul>	M <sup>2</sup>	80.64

		<p>apply two coats of premium quality primer</p> <ul style="list-style-type: none"> <li>• Apply two coats to an even finish of premium quality similar/ existing colour scheme internal wall paint.</li> </ul>		
5	Painting - Ceilings	<ul style="list-style-type: none"> <li>• Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>• Apply two coats to an even finish of premium quality similar/ existing colour scheme ceiling paint.</li> </ul>	M <sup>2</sup>	34.2
6	Painting - Doors & Trims	<ul style="list-style-type: none"> <li>• Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer.</li> <li>• Apply two coats of</li> </ul>	Each	4

		premium white gloss paint.		
Number	Item	Scope of works	Unit	Quantity
<b>Venue 5.4</b>				
7	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> <li>• Disconnect all water supply</li> <li>• Remove the existing water closet</li> </ul>	Each	2
8	Installation of WC	<ul style="list-style-type: none"> <li>• Installation of a complete junior Flush Master (premium quality to meet heavy traffic use)</li> </ul>	Each	2
9	Plumbing: Piping (Venue 5.4 & 5.5)	<ul style="list-style-type: none"> <li>• Replace existing copper piping with 22mm Copper</li> </ul>	M	10
	Elbows	<ul style="list-style-type: none"> <li>• Replace with 22mm copper</li> </ul>	Each	10
	T-Piece	<ul style="list-style-type: none"> <li>• Replace with 22mm copper</li> </ul>	Each	4
	Stop - Cock	<ul style="list-style-type: none"> <li>• Replace with 22mm copper</li> </ul>	Each	4
10	Painting – Floors	<ul style="list-style-type: none"> <li>• All floors to be thoroughly prepared to receive new floor coating</li> <li>• Apply two coats of polyurethane on floors as per the recommended factory application</li> </ul>	M <sup>2</sup>	27.36

11	Painting – Walls	<ul style="list-style-type: none"> <li>• Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>• Apply two coats to an even finish of premium quality similar/ existing colour scheme internal wall paint.</li> </ul>	M <sup>2</sup>	70.4
12	Painting - Ceilings	<ul style="list-style-type: none"> <li>• Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>• Apply two coats to an even finish of premium quality similar/ existing colour scheme ceiling paint.</li> </ul>	M <sup>2</sup>	70.4
13	Painting – Doors & Trims	<ul style="list-style-type: none"> <li>• Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of</li> </ul>	Each	4

		<ul style="list-style-type: none"> <li>premium wood primer.</li> <li>Apply two coats of premium white gloss paint.</li> </ul>		
Number	Item	Scope of works	Unit	Quantity
<b>Venue 10</b>				
14	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> <li>Disconnect all water supply</li> <li>Remove the existing water closet</li> </ul>	Each	2
15	Installation of WC	<ul style="list-style-type: none"> <li>Installation of a complete junior Flush Master (premium quality to meet heavy traffic use)</li> </ul>	Each	4
16	Plumbing: Piping (Venue 5.4 & 5.5)	<ul style="list-style-type: none"> <li>Replace existing copper piping with 22mm Copper</li> </ul>	M	20
	Elbows	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	10
	T-Piece	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	7
	Stop - Cock	<ul style="list-style-type: none"> <li>Replace with 22mm copper</li> </ul>	Each	8
17	Painting – Floors	<ul style="list-style-type: none"> <li>All floors to be thoroughly prepared to receive new floor coating</li> <li>Apply two coats of polyurethane on floors as</li> </ul>	Each	4

		per the recommended factory application		
Number	Item	Scope of works	Unit	Quantity
<b>Venue 3.8</b>				
18	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> <li>• Disconnect all water supply</li> <li>• Remove the existing water closet</li> </ul>	Each	4
19	Installation of WC	<ul style="list-style-type: none"> <li>• Installation of a complete junior Flush Master (premium quality to meet heavy traffic use)</li> </ul>	Each	4
20	Plumbing: Piping	<ul style="list-style-type: none"> <li>• Replace existing copper piping with 22mm Copper</li> </ul>	M	5
	Elbows	<ul style="list-style-type: none"> <li>• Replace with 22mm copper</li> </ul>	Each	15
	T-Piece	<ul style="list-style-type: none"> <li>• Replace with 22mm copper</li> </ul>	Each	3
	Stop - Cock	<ul style="list-style-type: none"> <li>• Replace with 22mm copper</li> </ul>	Each	4
21	Painting – Walls	<ul style="list-style-type: none"> <li>• Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>• Apply two coats to an even finish of premium</li> </ul>	M <sup>2</sup>	240

		quality similar/ existing colour scheme internal wall paint.		
22	Painting - Ceilings	<ul style="list-style-type: none"> <li>• Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>• Apply two coats to an even finish of premium quality similar/ existing colour scheme ceiling paint.</li> </ul>	M <sup>2</sup>	50.7
23	Painting – Doors & Trims	<ul style="list-style-type: none"> <li>• Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer.</li> <li>• Apply two coats of premium white gloss paint.</li> </ul>	Each	6
24	Electrical	<ul style="list-style-type: none"> <li>• Remove existing electrical light fitting and switch.</li> </ul>	Each	4



		<ul style="list-style-type: none"> <li>• Install round shaped (no less than 200mm) 6W LED fitting and PVC switch</li> </ul>		
Number	Item	Scope of works	Unit	Quantity
<b>Venue A2</b>				
25	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> <li>• Disconnect all water supply</li> <li>• Remove the existing water closet</li> </ul>	Each	6
26	Installation of WC	<ul style="list-style-type: none"> <li>• Installation of a complete Junior Flush Master (premium quality to meet heavy traffic use)</li> </ul>	Each	2
27	Plumbing: Piping	<ul style="list-style-type: none"> <li>• Replace existing copper piping with 22mm Copper</li> </ul>	M	6
	Elbows	<ul style="list-style-type: none"> <li>• Replace with 22mm copper</li> </ul>	Each	9
	T-Piece	<ul style="list-style-type: none"> <li>• Replace with 22mm copper</li> </ul>	Each	7
	Stop - Cock	<ul style="list-style-type: none"> <li>• Replace with 22mm copper</li> </ul>	Each	6
28	Painting – Walls	<ul style="list-style-type: none"> <li>• Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>• Apply two coats to an</li> </ul>	M <sup>2</sup>	5.04

		even finish of premium quality similar/ existing colour scheme internal wall paint.		
29	Painting - Ceilings	<ul style="list-style-type: none"> <li>• Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>• Apply two coats to an even finish of premium quality similar/ existing colour scheme ceiling paint.</li> </ul>	M <sup>2</sup>	50.4
30	Painting – Doors & Trims	<ul style="list-style-type: none"> <li>• Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer.</li> <li>• Apply two coats of premium white gloss paint.</li> </ul>	Each	2
<b>Number</b>	<b>Item</b>	<b>Scope of works</b>	<b>Unit</b>	<b>Quantity</b>
<b>Venue A1</b>				

31	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> <li>• Disconnect all water supply</li> <li>• Remove the existing water closet</li> </ul>	Each	8
32	Installation of WC	<ul style="list-style-type: none"> <li>• Installation of a complete junior Flush Master (premium quality to meet heavy traffic use)</li> </ul>	Each	8
27	Plumbing: Piping	<ul style="list-style-type: none"> <li>• Replace existing copper piping with 22mm Copper</li> </ul>	M	8
	Elbows	<ul style="list-style-type: none"> <li>• Replace with 22mm copper</li> </ul>	Each	10
	T-Piece	<ul style="list-style-type: none"> <li>• Replace with 22mm copper</li> </ul>	Each	7
	Stop - Cock	<ul style="list-style-type: none"> <li>• Replace with 22mm copper</li> </ul>	Each	8
28	Painting – Walls	<ul style="list-style-type: none"> <li>• Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>• Apply two coats to an even finish of premium quality similar/ existing colour scheme internal wall paint.</li> </ul>	M <sup>2</sup>	50.4

29	Painting - Ceilings	<ul style="list-style-type: none"> <li>• Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer</li> <li>• Apply two coats to an even finish of premium quality similar/ existing colour scheme ceiling paint.</li> </ul>	M <sup>2</sup>	32
30	Painting – Doors & Trims	<ul style="list-style-type: none"> <li>• Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer.</li> <li>• Apply two coats of premium white gloss paint.</li> </ul>	Each	1

The quotations are to be submitted to the SCM Unit.


N.Ngxekana




N Ngxekana

AD: Infrastructure Construction and Maintenance

Date: 03/05/2022

  
.....  
Z Chofa  
DP : Corporate Services  
Date: 04/05/2022

S.Siwisa

  
.....  
A.D : SCM  
Date: 04/05/2022