



higher education
& training
Department
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



BUFFALO CITY
TVET COLLEGE

REQUEST FOR QUOTATIONS AND SITE BRIEFING FOR JKB TOILET FACILITIES

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to quotations@bccollege.co.za

Kindly submit the following **REQUIRED** documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Declaration forms (SBD 4, 8 and 9)
- Certified BEE certificate (0 points will be awarded for BEE certificates that are not certified)
- Tax Clearance Certificate
- CSD report
- Bank Confirmation Letter (not older than 3 months)
- **Quotations must be detailed as the specification**

N. B. Compulsory site briefing session will be held at John Knox Bokwe Campus on 07 June 2022 @ 09 Am.

Closing Date: 15 June 2022 at 11:00 Am. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED

Enquiries: Ms Weziwe Gwabavu / Zimkhitha Jikwana

043 704 9241



higher education
& training

Department
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



BUFFALO CITY
TVET COLLEGE

Date: 31 May 2022

Enquiries: nnizakana@bccollege.co.za

Delivery Date : (within two week from issuing of purchase order)

REPAIRS AND MAINTENANCE TO TOILET FACILITIES – JOHN KNOX BOKWE CAMPUS

Number	Item	Scope of works	Unit	Quantity
Venue 5.5				
1	Removal of existing water closet (Toilet)	<ul style="list-style-type: none">• Disconnect all water supply• Remove the existing water closet	Each	2
2	Installation of WC	<ul style="list-style-type: none">• Installation of a complete junior Flush Master (premium quality to meet heavy traffic use)	Each	2
3	Painting – Floors	<ul style="list-style-type: none">• All floors to be thoroughly prepared to receive new floor coating• Apply two coats of polyurethane on floors as per the recommended factory application	M ²	34.2
4	Painting – Walls	<ul style="list-style-type: none">• Prepare the surface of any cracks and imperfections,	M ²	80.64

		<p>apply two coats of premium quality primer</p> <ul style="list-style-type: none"> Apply two coats to an even finish of premium quality similar/ existing colour scheme Internal wall paint. 		
5	Painting - Ceilings	<ul style="list-style-type: none"> Prepare the surface of any cracks and Imperfections, apply two coats of premium quality primer Apply two coats to an even finish of premium quality similar/ existing colour scheme ceiling paint. 	M ²	34.2
6	Painting - Doors & Trims	<ul style="list-style-type: none"> Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer. Apply two coats of 	Each	4

		premium white gloss paint.		
Number	Item	Scope of works	Unit	Quantity
Venue 5.4				
7	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> • Disconnect all water supply • Remove the existing water closet 	Each	2
8	Installation of WC	<ul style="list-style-type: none"> • Installation of a complete Junior Flush Master (premium quality to meet heavy traffic use) 	Each	2
9	Plumbing: Piping (Venue 5.4 & 5.5)	<ul style="list-style-type: none"> • Replace existing copper piping with 22mm Copper 	M	10
	Elbows	<ul style="list-style-type: none"> • Replace with 22mm copper 	Each	10
	T-Piece	<ul style="list-style-type: none"> • Replace with 22mm copper 	Each	4
	Stop - Cock	<ul style="list-style-type: none"> • Replace with 22mm copper 	Each	4
10	Painting – Floors	<ul style="list-style-type: none"> • All floors to be thoroughly prepared to receive new floor coating • Apply two coats of polyurethane on floors as per the recommended factory application 	M ²	27.36

11	Painting – Walls	<ul style="list-style-type: none"> • Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer • Apply two coats to an even finish of premium quality similar/ existing colour scheme internal wall paint. 	M ²	70.4
12	Painting - Ceilings	<ul style="list-style-type: none"> • Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer • Apply two coats to an even finish of premium quality similar/ existing colour scheme ceiling paint. 	M ²	70.4
13	Painting – Doors & Trims	<ul style="list-style-type: none"> • Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of 	Each	4

		<p>premium wood primer.</p> <ul style="list-style-type: none"> Apply two coats of premium white gloss paint. 		
Number	Item	Scope of works	Unit	Quantity
Venue 10				
14	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> Disconnect all water supply Remove the existing water closet 	Each	7
15	Installation of WC	<ul style="list-style-type: none"> Installation of a complete junior Flush Master (premium quality to meet heavy traffic use) 	Each	7
16	Plumbing: Piping (Venue 5.4 & 5.5)	<ul style="list-style-type: none"> Replace existing copper piping with 22mm Copper 	M	20
	Elbows	<ul style="list-style-type: none"> Replace with 22mm copper 	Each	10
	T-Piece	<ul style="list-style-type: none"> Replace with 22mm copper 	Each	7
	Stop - Cock	<ul style="list-style-type: none"> Replace with 22mm copper 	Each	8
		<ul style="list-style-type: none"> 		
Number	Item	Scope of works	Unit	Quantity
Venue 3.8				
17	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> Disconnect all water supply Remove the existing water closet 	Each	4

18	Installation of WC	<ul style="list-style-type: none"> Installation of a complete junior Flush Master (premium quality to meet heavy traffic use) 	Each	4
19	Plumbing: Piping	<ul style="list-style-type: none"> Replace existing copper piping with 22mm Copper 	M	5
	Elbows	<ul style="list-style-type: none"> Replace with 22mm copper 	Each	15
	T-Piece	<ul style="list-style-type: none"> Replace with 22mm copper 	Each	3
	Stop - Cock	<ul style="list-style-type: none"> Replace with 22mm copper 	Each	4
20	Painting – Walls	<ul style="list-style-type: none"> Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer Apply two coats to an even finish of premium quality similar/ existing colour scheme internal wall paint. 	M ²	24
21	Painting - Ceilings	<ul style="list-style-type: none"> Prepare the surface of any cracks and imperfections, apply two coats of 	M ²	50.7

		<p>premium quality primer</p> <ul style="list-style-type: none"> Apply two coats to an even finish of premium quality similar/ existing colour scheme ceiling paint. 		
22	Painting – Doors & Trims	<ul style="list-style-type: none"> Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer. Apply two coats of premium white gloss paint. 	Each	6
23	Electrical	<ul style="list-style-type: none"> Remove existing electrical light fitting and switch. Install round shaped (no less than 200mm) 6W LED fitting and PVC switch 	Each	4
Number	Item	Scope of works	Unit	Quantity
Venue A2				
24	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> Disconnect all water supply 	Each	6

		<ul style="list-style-type: none"> Remove the existing water closet 		
25	Installation of WC	<ul style="list-style-type: none"> Installation of a complete Junior Flush Master (premium quality to meet heavy traffic use) 	Each	6
26	Plumbing: Piping	<ul style="list-style-type: none"> Replace existing copper piping with 22mm Copper 	M	6
	Elbows	<ul style="list-style-type: none"> Replace with 22mm copper 	Each	9
	T-Piece	<ul style="list-style-type: none"> Replace with 22mm copper 	Each	7
	Stop - Cock	<ul style="list-style-type: none"> Replace with 22mm copper 	Each	6
27	Painting – Walls	<ul style="list-style-type: none"> Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer Apply two coats to an even finish of premium quality similar/ existing colour scheme internal wall paint. 	M ²	54
28	Painting - Ceilings	<ul style="list-style-type: none"> Prepare the surface of any 	M ²	50.4

		<p>cracks and imperfections, apply two coats of premium quality primer</p> <ul style="list-style-type: none"> Apply two coats to an even finish of premium quality similar/ existing colour scheme ceiling paint. 		
29	Painting -- Doors & Trims	<ul style="list-style-type: none"> Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer. Apply two coats of premium white gloss paint. 	Each	2
Number	Item	Scope of works	Unit	Quantity
Venue A1				
30	Removal of existing water closet (Toilet)	<ul style="list-style-type: none"> Disconnect all water supply Remove the existing water closet 	Each	8
31	Installation of WC	<ul style="list-style-type: none"> Installation of a complete Junior Flush Master (premium 	Each	8

		quality to meet heavy traffic use)		
32	Plumbing: Piping	<ul style="list-style-type: none"> Replace existing copper piping with 22mm Copper 	M	8
	Elbows	<ul style="list-style-type: none"> Replace with 22mm copper 	Each	10
	T-Piece	<ul style="list-style-type: none"> Replace with 22mm copper 	Each	7
	Stop - Cock	<ul style="list-style-type: none"> Replace with 22mm copper 	Each	8
33	Painting – Walls	<ul style="list-style-type: none"> Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer Apply two coats to an even finish of premium quality similar/ existing colour scheme internal wall paint. 	M ²	50.4
34	Painting - Ceilings	<ul style="list-style-type: none"> Prepare the surface of any cracks and imperfections, apply two coats of premium quality primer Apply two coats to an even finish of 	M ²	32

		premium quality similar/ existing colour scheme ceiling paint paint.		
35	Painting – Doors & Trims	<ul style="list-style-type: none"> • Prepare the surface of all doors and trims to a smooth, even finish, and apply two coats of premium wood primer. • Apply two coats of premium white gloss paint. 	Each	1

The quotations are to be submitted to the SCM Unit.

N. Ngxekana



N Ngxekana

AD: Infrastructure Construction and Maintenance

Date: 30/05/2022

ZChola

DP : Corporate Services

Date: 31/05/2022

S.Siwisa



AD : SCM

Date: 01/06/2022