



REQUEST FOR QUOTATIONS AND SITE BRIEFING FOR SERVICING OF AIRCONS (ADM)

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to quotations@bccollege.co.za

Kindly submit the following REQUIRED documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Declaration forms (SBD 4, 8 and 9)
- Certified BEE certificate (0 points will be awarded for BEE certificates that are not certified)
- Tax Clearance Certificate
- CSD report
- Bank Confirmation Letter (not older than 3 months)
- Quotations must be detailed as the specification

N. B. Compulsory site briefing session will be held at Admin Centre on 11 July 2022 @ 12 Pm.

Closing Date: 19 July 2022 at 11:00 Am. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED

Enquiries: Ms Weziwe Gwabavu / Zimkhitha Jikwana

043 704 9241







Relevant Societional Effication for Changing World

TO

WHOM IT MAY CONCERN

FROM:

BUFFALO CITY TVET COLLEGE

SUBJECT:

REQUEST FOR PRICE QUOTATION

Kindly provide Buffalo City TVET College with a quotation as per the specification below:

Location	Size	QTY	Description
Ground Floor			
AD26	12 000BTU	1	AIR HANDLING UNIT
AD33	12 000 BTU	2	Remove and clean filters
AD28	12 000 BTU	3	Check filter pressure drops within clean range on
HR SDF OFFICE	12 000 BTU	1	
AD23	14 000 BTU	1	Magnehelic/ Manometer gauge
AD21	12 000 BTU	1	Check all components for
AD20	12 000 BTU	3	corrosion, clean and treat
AD27	12 000 BTU	1	Clean out fresh air intake grille
INFRASTRUCTURE	12 000 BTU	2	and coil
KITCHEN	18 000 BTU	1	Check condition of fan belts
ACADEMIC	18 000 BTU	1	and adjust tension
OUTSIDE OFFICE			Check bearings for sweating. Lubringto bearings.
			Lubricate bearings, bushes, dampers and other moving
FIRST FLOOR			parts and other moving
MARKETING	12 000 BTU	3	Clean drip-pan and drain line -
FINANCE	12 000 BTU	1	test all
MANAGER		1	Clean fan compartment
STAKE HOLDER	12 000 BTU	1	Clean evaporator coil
OFFICE			Check fan / motor mounting
ACADEMIC DP	12 000 BTU	1	and tighten
OPEN AREA	18 000 BTU	1	 Check all components for
FINANCE DP	12 000 BTU	1	excessive noise and vibration
SSS DP	12 000 BTU	1	Check and record evaporator
CORPORATE	12 000 BTU	1	fan amps Check and record overload set
SERVICES		1	
SCM MANAGER	12 000 BTU	1	point
PRINCIPAL	12 000 BTU	1	Check control panel for correct
OFFICE			operation, loose connections, labels, corrosion and
PRINCIPAL	12 000 BTU	1	Cleanliness
SECRETARY			South milition

- Check motor connections are tight
- Record on / off coil temperatures
- Check DX Coil not freezing indicating low air flow or under charge
- Supply fan runs down after unit switched off on unit fitted with heaters
- Heaters come on if set point adjusted
- Supply fan runs down after unit switched off on unit fitted with heaters
- Check condition of unit insulation
- Check door seals and hinges
- Record overheat stat settings
- Check air flow / pressure switch is working
- Record on/off coil temperatures

CONDENSING UNIT

- Clean and check condenser coils
- Record outside air temperature
- Record suction pressure
- Record discharge pressure
- Record liquid level in site glass
- Check for refrigerant leaks
- Check condition of refrigeration lines and insulation
- Record low pressure trip set point
- Record high pressure trip set point
- Adjust controller and check reverse value
- Record compressor operating amps
- Record compressor overload trip set point
- Check motor connections are tight
- Check all components for corrosion and treat
- Check operation of fire relay
- Check humidifier bottles are clean and free or corrosion and

dirty water

 Check humidifier is functioning when set point adjusted and does not drain frequently

DUCTING

- Check condition of all ducting and duct fixings
- Check integrity of all joints
- Check condition of duct insulation
- Check all heater connections and operation of heaters
- Check and clean all supply and return air grilles
- Damper actuators not stuck and are operating

CONDITIONED SPACE

- Record controller temperature set points
- Record conditioned space temperature
- Record supply air temperature
- Record return air temperature

ELECTRICAL INSTALLATION

- Check all electrical terminations are tight
- Check all terminal boxes are watertight
- Check all equipment is bonded to the earthing system
- Check heater elements and replace if necessary
- Check element load ratings
- Check all protection devices are installed and operating

A compulsory site inspection will take place as determined by the SCM unit.

Kind regards

N.Ngxekana

A.D. Intractructure

Z. Chora

S. Siwisa

MSucia A.D: SCM Date: 27/06/2022