



higher education
& training
Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



BUFFALO CITY
TVET COLLEGE

**REQUEST FOR QUOTATIONS AND SITE BRIEFING FOR REPAIRS AND
MAINTENANCE OF GLOUCESTER HOUSE HOSTEL**

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to quotations@bccollege.co.za

Kindly submit the following **REQUIRED** documents when responding to the RFQ

- Signed quotation (quotations not signed will be eliminated)
- Declaration forms (SBD 4, 8 and 9)
- Certified BEE certificate (0 points will be awarded for BEE certificates that are not certified)
- Tax Clearance Certificate
- CSD report
- Bank Confirmation Letter (not older than 3 months)
- **Quotations must be detailed as the specification**

N. B. Compulsory site briefing session will be held at Gloucester house hostel on Monday 18 July 2022 @ 14:45

Closing Date: 22 July 2022 at 11:00 Am. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED

Enquiries: Ms Weziwe Gwabavu / Zimkhitha Jikwana

043 704 9241



higher education
& training

Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



BUFFALO CITY
TVET COLLEGE

Date: 02 – 06 -2022

Enquiry: Infrastructure Unit – 043 704 9255


REPAIRS AND MAINTENANCE OF GLOUCESTER HOUSE HOSTEL

No	Item	Scope of Works	Unit	QTY
Toilet 1 (Old Principal House)				
1	Extractor Fan	<ul style="list-style-type: none"> Cut out opening for ceiling mounted extractor fan (subject to design and size) 	Each	1
		<ul style="list-style-type: none"> Allow for new installation of timber brandering to accommodate extractor fan brackets 	Item	1
		<ul style="list-style-type: none"> Supply and fit new extractor fan (Minimum 60W) 	Each	2
2	Plastering	<ul style="list-style-type: none"> Plaster all imperfections 	Item	1
3	Painting	<ul style="list-style-type: none"> Apply two coats of premium quality primer on walls 	M ²	7
		<ul style="list-style-type: none"> Apply two coats of existing PVA low sheen paint on walls 	M ²	7
		<ul style="list-style-type: none"> Apply two coats of premium primer on ceilings 	M ²	6.24
		<ul style="list-style-type: none"> Apply two coats of premium white paint of ceilings 	M ²	6.24
4	Ducting	<ul style="list-style-type: none"> Cut out 110mm round hole for air ducting from ceiling onto side exterior wall (to be viewed onsite) 	Each	2
		<ul style="list-style-type: none"> Supply 100mm flexible aluminium foil ducting 	Each	2
		<ul style="list-style-type: none"> All ducting to be neatly clamped inside ceiling 	Item	1
		<ul style="list-style-type: none"> Supply and fit stainless steel square wall air vent ducting grill cover (100mm) 	Each	2
5	Electrical	<ul style="list-style-type: none"> Supply and run 1.5mm Twin & Earth onto 	M	10

		<ul style="list-style-type: none"> isolator and onto electrical light switch All electrical to be neatly clamped and sealed off with water/ steam resistant substance in joints and connections 	Item	1
External Toilets				
6	Extractor Fan	<ul style="list-style-type: none"> Cut out opening for wall mounted extractor fan (subject to design and size) Supply and fit new extractor fan (Minimum 60W) 	Item	5
			Each	5
7	Electric	<ul style="list-style-type: none"> Supply and run 1.5mm Twin & Earth onto isolator and onto electrical light switch All electrical to be neatly clamped and sealed off with water/ steam resistant substance in joints and connections 	M	10
			Item	1
8	Plastering	<ul style="list-style-type: none"> Plaster all imperfections 	Item	1
9	Painting	<ul style="list-style-type: none"> Apply two coats of premium primer on walls Apply two coats of existing PVA low sheen paint on walls Apply two coats of premium primer on ceilings Apply two coats premium white ceiling paint 	M ²	15
			M ²	15
			M ²	8.85
			M ²	8.85
10	Curtain Rails	<ul style="list-style-type: none"> Remove existing curtain rails and install no less than 200 mm round aluminium rails (x2 units) 	M	1.46
Razor Security Wire				
11	Razor wire	<ul style="list-style-type: none"> Installation of galvanised steel razor wire as per the following spec: Core diameter : 2.5mm Coil diameter : 450mm Blade thickness 1.5mm Blade length 42mm Blade width 30mm 	M	190

		<ul style="list-style-type: none"> • Blade space 21mm • Number loops : 55 loops per 100 wire with 3 – 5 clips per loop 		
12	Flooring	<ul style="list-style-type: none"> • Prepare existing floor covering to receive new floor covering • Installation of (300 x 300mm) vinyl tiles (Glued on) 	M ²	30

N.B: A compulsory site briefing will be held as per the date indicated on the advert.


.....

N.Ngxekana
A.D: Infrastructure

07/07/2022
.....
Date.


.....

Z.Chole
DP : Corporate Services

07/07/2022
.....
Date.


.....

S.Siwisa
A.D : Procurement

12/07/2022
.....
Date