



higher education
& training
Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



BUFFALO CITY
TVET COLLEGE

REQUEST FOR QUOTATIONS – MINOR REPAIRS AND MAINTENANCE TO
GLOUCESTER HOUSE RESIDENCE

Kindly see the attached request for quote (RFQ). Quotations should be forwarded to quotations@bccollege.co.za.

TENDERERS MUST NOTE THAT WHEREVER THIS DOCUMENT REFERS TO ANY PARTICULAR TRADE MARK, NAME, PATENT, DESIGN, TYPE, SPECIFIC ORIGIN OR PRODUCER, SUCH REFERENCE SHALL BE DEEMED TO BE ACCOMPANIED BY THE WORDS 'OR EQUIVALENT.

Kindly submit the following **REQUIRED** documents when responding to the RFQ

1. Signed quotation (quotations not signed will be eliminated)
2. Latest declaration forms (SBD 4, 8 and 9), see attached on college website
3. Certified BBBEE certificate (0 points will be awarded for BBBEE certificates that are not certified)
4. Tax Clearance Certificate
5. CSD full report
6. Company Registration
7. Bank Confirmation Letter (not older than 3 months)
8. Quotations must be detailed as per specification
9. CIDB registration of 1GB or higher
10. Quotations must be submitted in the PDF format **ONLY**
11. All quotations submitted via email addresses other than the one listed above will not be considered.

Closing Date 24 OCTOBER 2024 at 11h00 am. No late or hand delivered documents will be accepted. ONLY EMAILED DOCUMENTS WILL BE ACCEPTED

043 704 9238 / 043 704 9241



**higher education
& training**

Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



**BUFFALO CITY
TVET COLLEGE**

Date: 15 October 2024

Enquiries: nngxekana@bccollege.co.za


MINOR REPAIRS AND MAINTENANCE FOR GLOUCESTER HOUSE RESIDENCE

Buffalo City TVET College hereby request a priced quotation from suitable contractors for the **Minor repairs and maintenance for Gloucester House**. Contractors whom are registered with the **CIDB Grade 1GB or higher registration may apply (attach the certificate)**.

Number	Item	Description	Unit	Quantity
1.	Painting of internally walls. (Main Building and External Buildings)	<ul style="list-style-type: none">• Prepare the wall and apply three coats of high quality interior matt finish (same as existing colour) to a smooth finish.	M2	200
2.	Painting Internally all Bathrooms.(Main Building, Annex Building, Bathroom External Buildings)	<ul style="list-style-type: none">• Prepare the wall and apply three coats of high quality premium aqua velvet pastel.	M2	100
3.	Painting (Ceilings Main Building, Annex Building, Bathroom External Buildings)	<ul style="list-style-type: none">• Prepare ceiling and ply two coats premium primer.• Apply two coats of premium white paint of ceilings.	M2	100
4	Door	<ul style="list-style-type: none">• Remove and replace existing normal door for internal use (Standard door size)	Item	4
5	Door	<ul style="list-style-type: none">• Door lock set with handles.)	Item	5
6	Cleaning of Aluminum windows	<ul style="list-style-type: none">• Cleaning of Aluminum windows and allowance of hiring Scaffolding for	No	58

		high heights.		
7.	Cleaning of Steel windows	<ul style="list-style-type: none"> Cleaning of Steel windows and allowance of hiring Scaffolding for high heights. 	No	75
8.	Matron Office (window tinting)	<ul style="list-style-type: none"> Tinting of existing glass window pane and smash grab (20% shade) 	M2	5
9	Main Building and External House.	<ul style="list-style-type: none"> Remove and install shower heads set and arms. Remove and install star silver tap for showers 	No No	6 6
10.	Main Building and External House.	<ul style="list-style-type: none"> Supply and install Toilet flushing Cistern white including internal flushing mechanism and flush pipe. 	No	6
11.	Main Building, External House and Annex Building.	<ul style="list-style-type: none"> Supply and Install Coral white Top fit Toilet seat pans. 	No	5
11.	Glazing	<ul style="list-style-type: none"> Remove existing and Installation new glazing for broken windows. 	M2	4
	Door (Varnish)	<ul style="list-style-type: none"> Prepare one coat universal undercoat and two coats superior quality eggshell enamel on to Doors (both side measured) 	M2	50
	Security Fence (Internally)	<ul style="list-style-type: none"> Remove existing concrete panels and take away the rubbish from site. 	M	13
12.	Security Fence (Internally)	<ul style="list-style-type: none"> Installation on new Diamond mash 2200x100x100 Installation of new 2400x100 mint road tinted round pole. 	M No	15 9

		<ul style="list-style-type: none"> Dig 600 mm for installation of pole and allowance of concrete to make smooth finish. 	No	9
		<ul style="list-style-type: none"> Installation of fence Barbed wire single strand Roll (size 2mm) Nails for installation of fence wire. Nails for installation of fence wire. 	28.5 kg 4 kg 5 kg	1 3 3
13	Galvanize gate	<ul style="list-style-type: none"> Installation of Galvanize Palisade Gate with spikes on top 2000height and 3300width. 	No	1
	Shower Curtains	<ul style="list-style-type: none"> 1.00 m and 1.90 length shower curtain fabric. 	No	10
13.	Servicing of roofs (Kitchen and Staff room)	<ul style="list-style-type: none"> Provisionally Sum 	Item	R10 000
14	Electrical work	<ul style="list-style-type: none"> Provisionally Sum 	Item	R20 000
15		SUB - Total	R	
		Add 10% of Preliminaries from Contract Amount	R	
		Vat 15%	R	
		Total (Inclusive of Vat)	R	



N Ngxekana

Project Manager: Infrastructure

Date: _____



Z. Chola

DP: Corporate Services

Date: 15/10/2024



B. Timothy

SCM Manager

Date: 16/10/2024